

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-19281-00-00
Spot: SESWE Sec/Twnshp/Rge: 12-26S-14E
165 feet from S Section Line, 1760 feet from E Section Line
Lease Name: ONNEN LEASE Well #: 5
County: WOODSON Total Vertical Depth: 1147 feet

Operator License No.: 9672
Op Name: ONNEN, GERHARD E.
Address: 862 50TH RD.
YATES CENTER, KS 66783

PROD Size: 2.875 feet: 1147
SURF Size: 7 feet: 40

A 37²⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2004 9:00 AM
Plug Co. License No.: 4845 Plug Co. Name: EDWIN SHERMAN DBA F & S OIL
Proposal Rcvd. from: HERB FEIF Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO 1125' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2 7/8" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: PARTIAL
Date/Time Plugging Completed: 03/22/2004 1:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 1125'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 34 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
JUN 14 2004
KCC WICHITA

RECEIVED
KCC District #3
JUN 9 2004 *BL*
Chanute, KS

Remarks:

Plugged through:

District: 03

Signed Clayton Titel by BL
(TECHNICIAN)
INVOICED
DATE 6-15-04
INV. NO. 2004061670