

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-137-20,388-⁰⁰⁻⁰⁰ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Chaco Energy Company (owner/company name) KCC LICENSE # 31217 (operator's)

ADDRESS P.O. Box 1587 CITY Denver

STATE Colorado ZIP CODE 80201 CONTACT PHONE # (303) 744-1480

LEASE Blickenstaff WELL# 1-15 SEC. 5 T. 2S R. 24 (East/West)

- SW - SW - SW SPOT LOCATION/QQQQ COUNTY Norton

330' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

330' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 289' CEMENTED WITH 60-40 posmix-175 sx SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION _____ (G.L./K.B.) T.D. 3796' PBSD _____ ANHYDRITE DEPTH 2064'-2091' (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2070' w/25 sx; 2nd plug @ 1300' w/100 sx; 3rd plug @ 340' w/40 sx; 4th plug @ 40' w/solid bridge w/10 sx; rathole 15 sx. Total 190 sx 60-40 posmix 6% gel 3% cc.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No

If not explain why? Sent to Operator to complete.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Fisher PHONE# (913) 743-5654

ADDRESS 333 N. 2nd Street City/State Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684
(company name) (contractor's)

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If known?) Began @ 6:30 a.m. 6-21-93.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/3/93 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

8-4-93