

46
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00272-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1963
10-9-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name H. P. McLish,
Complete Address: 704 Patterson Building, Denver, Colorado.
Lease Name Miller Well No. 1
Location CSE-NW Sec. 31 Twp. 2 Rge. (E) (W) 24
County Norton Total Depth 3809
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: National Drilling Company,
Address: 531 Petroleum Building, Wichita, Kansas. License No.
Operation Completed: Hour 6:00PM Day 6 Month 10 Year 1963

The Above well was plugged as follows:

257'--8 5/8" Surface pipe, cement circulated.
Circulated hole with heavy mud, set plug @ 550' with 1/4 Sk hulls & dis-
placed 20 Sx cement thru DP. Heavy mud to 250', set plug with 1/4 Sk hulls
and displaced 20 Sx cement thru DP. Heavy mud to 40', set plug with 1/2
Sk hulls and 10 Sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/10/63
INV. NO. 7862-W

Signed: *W. L. Nichols*
Well Plugging Supervisor