

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-137-20040-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
1-12-70

Operator's Full Name Murfin Drilling Company,  
Complete Address 617 Union Center Building, Wichita, Kansas.  
Lease Name Preston Well No. 1  
Location SE-SE-SW Sec. 1 Twp. 2 Rge. (E) (W) 25  
County Norton Total Depth 3768'  
Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Above  
Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 4:45 PM Day 7 Month 1 Year 1970

The above well was plugged as follows:

375'--8 5/8" Surface casing, cement circulated.  
Circulated hole with heavy mud. Pulled DP to 920' and displaced 90 Sx. cement thru  
DP from 920' to 620'. Pulled DP to 370' and displaced 35 Sx. cement thru DP from  
370' to 270'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 1/12/70  
INV. NO. 1236-4