

LEASE NAME COULTER

WELL NUMBER #1

2970 Ft. from S Section Lin.

330 Ft. from E Section Lin.

SEC. 12 TWP. 26 SRGE. 12 (E) or (C)

COUNTY PRATT

Date Well Completed 9/15/81

Plugging Commenced 1/10/98

Plugging Completed 1/21/98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR LYONS & LYONS, INC.

ADDRESS 1519 S. BALTIMORE AVE, TULSA, OK 74119

PHONE# (918) 587-2497 OPERATORS LICENSE NO. 31465

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/16/98 (date)

by STEVE PFIEFER (KCC District Agent's Name)

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation VIOLA Depth to Top 4142 Bottom 4146 T.O. 4373

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
VIOLA	OIL, GAS & WATER	0	402	8 5/8"	8/7/81	LEFT
		0	4371'	4 1/2"	8/18/81	516' on 1/20/98

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s.

RAN TUBING TO 1285', SPOT 50 SX 3% CACI CEMENT, LET SET 2 HRS. RAN TBG STOPPED @ 975'  
SPOTTED @ 975' 50 SX 3% CACI CEMENT, CHECKED WITH WIPELINE T/CEMENT 600'. SHOT PIPE OFF @ 516'  
PULLED 516' CASING. SPOTTED 50 SX 3% CACI CEMENT @ 422'. RAN TUBING TO 324' CIRCULATED CEMENT  
TO SURFACE. PULLED TUBING AND FILLED HOLE WITH CEMENT.

Name of Plugging Contractor PRATT WELL SERVICE

Address P.O. Box 847, PRATT, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: LYONS & LYONS, INC.

APR 16 1998

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

4-16-98  
CONSERVATION DIVISION  
WICHITA, KS

TREVOR M. LYONS

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Trevor M. Lyons

(Address) 1519 S. BALTIMORE AVE.

SUBSCRIBED AND SWORN TO before me this 8th day of APRIL, 19 98

Philip W. Stuyck OK 96009316  
Notary Public

My Commission Expires: 6-11-2000

USE ONLY ONE SIDE OF EACH FORM