

15-007-20530-0000

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD KAR. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License # 34926 Name: R.K.R. Production Company Address 1: Address 2: P.O. Box 295 City: Mustang State: Ok Zip: 73064 Contact Person: Gary Craighead Phone: (405) 376-2223 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Mississippian Depth to Top: 4820' Bottom: 4840' T.D. N.A.

API No. 15 - 007-20530-00-00 Spot Description: C-12 SW Sec 7 Twp 34 S. R 13 East West 1980 Feet from North / South Line of Section 3960 Feet from East / West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Barber Lease Name: Clarke Well #: 1 Date Well Completed: The plugging proposal was approved on: 8/30/2018 (Date) by: Steve Pfeifer (KCC District Agent's Name) Plugging Commenced: 8/31/2018 Plugging Completed: 9/6/2018

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Handwritten entries include surface casing at 8.425" size and production casing at 2.75" size, both with a setting depth of 5347' and pulled out 1000'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run 1.667 tubing in to 2200' - Pumped 20 sx common cement - Shot 2 7/8 casing off at 1000' - Pulled up to 740' pumped 10 sx gel - 50 sx 60/40 4 9/16 gel - Pulled up to 380' pumped 50 sx cement - Pulled up to 60' pumped and circulated to surface 30 sx cement to surface - Top off with 5 sx

Plugging Contractor License #: 5105 Name: Clarke Corporation Address 1: 107 West Fowler Address 2: City: Medicine Lodge State: Kansas Zip: 67104 + 1534 Phone: (320) 886-5665 Name of Party Responsible for Plugging Fees: RKR Production Company State of Oklahoma County: Canadian ss. Gary Craighead (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Morganster

Received KANSAS CORPORATION COMMISSION SEP 24 2018 CONSERVATION DIVISION WICHITA, KS