

1 030580

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,985 **R**
70' N + 45' E of
C 5 1/2 SE NW, SEC. 25, T 30 S, R 12 W/E

3255 feet from S section line
3040 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Thom Well # 1-25

Operator: TEXAS ENERGIES, INC

County Barber 146.25

Name & Address Box 947

Well Total Depth 4500 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 310

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso casing plugging License Number 6050

Address Box 947 Phase 1CS, 67124

Company to plug at: Hour: 5:00 PM Day: 20 Month: 11 Year: 1985

Plugging proposal received from Ted MOFF

(company name) TEXAS ENERGIES (phone) 672-9581

were: 4 1/2" set @ 4477 w/ 250SX - TOP Reys @ 4357-4360'

Sand bottom reys to 4300' + dump 45X cement through bailer.

Recover casing and squeeze well through 8 7/8 plug

return + shut in. 30X hulls → 10SX gul → 50SX cement →

10SX gul → 1 hull → 8 7/8 plug → 125SX cement -

Plugging Proposal Received by Steve Dumont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:25 PM Day: 20 Month: 11 Year: 1985

ACTUAL PLUGGING REPORT Bottom plug @ 4300' w/ sand + 45X cement

on reys. Sand on dirt bridge in hole - could not plug

into well. Change order to spot plugs through tubing:

Load hole w/ mud @ 900' + spot cement through tubing

1st plug @ 900' w/ 50SX 3rd 40' to 60' w/ 10SX

2nd plug @ 360' w/ 50SX mud between all plugs.

Remarks: Washburn 6/40 002

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 10 1985

INV. NO. 11382

CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Dumont
(TECHNICIAN)

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,985

LEASE NAME Thom 1-25

WELL NUMBER _____

SPOT LOCATION 70'N, 45'E C S/2 SE
NW

SEC. 25 TWP. 30 S RGE. 12 W (E) or (W)

COUNTY Barber

Date Well Completed _____

Plugging Commenced 9/24/85

Plugging Completed 11/20/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texas Energies, Inc.

ADDRESS Box 947, Pratt, Ks. 67124

PHONE # (316) 672-7514 OPERATORS LICENSE NO. 5087

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	310'	none
				4 1/2"	4477'	2882'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4300' & 4 sacks cement. Shot pipe at 3408' 3203', 3126', & 2882'. Pulled 71 joints of pipe. Plugged well with 50 sacks cement @ 936', filled with mud from 700' to 360'. Ran 50 sack plug @ 360', ran 15 sacks 60/40 poz 6% gel @ 40' to surface. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of November, 1985

Irene Hoover
Notary Public



My Commission expires:

NOV 25 1985