

KCC OIL/GAS REGULATORY OFFICES

Date: 03/28/18

District: 01

Case #: _____

New Situation

Lease Inspection

Response to Request

Complaint

Follow-Up

Field Report

Operator License No: 30535

API Well Number: 15-055-21853-00-01

Op Name: Hartman Oil Co

Spot: NW NE Sec 21 Twp 22 S Rng 33 E / W

Address 1: 10500 E Berkeley Sq Pkwy, Ste 100

660 Feet from N / S Line of Section

Address 2: _____

1820 Feet from E / W Line of Section

City: Wichita

GPS: Lat: _____ Long: _____ Date: _____

State: Kansas Zip Code: 67206

Lease Name: Damme Well #: 37 OWWO

Operator Phone #: 316 636 2090

County: Finney

Reason for Investigation:

Alternate 2 cementing

Problem:

This was a re-entry of an old hole. While drilling out the cement plugs, the drilling rig got out of the old hole in the 1100-1200' range, then drilled a new hole to TD.

Persons Contacted:

Kent Strube

Findings:

3/26/18 8 5/8 @ 318', 5 1/2 @ 4872' w/ 140 sx. TD @ 4900', Port collar @ 2611'. QES pumped 275 sx 60/40 poz 8% gel w/ 400 # cottonseed hulls thru port collar. No blow or circulation up the annulus. Close port collar, reverse out cmt & TOOH w/ tbg.

3/28/18 Pioneer ran CBL. Found bottom of cmt @ 2706' & top of cmt @ 1577'. Stone Corral is covered. Perf 4 holes @ 948'. QES pumped 145 sx 60/40 poz 8% gel followed by 50 sx CI A common thru perms. Circulated 30 sx to the pit.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

Alternate 2 cmtg complete.

Verification Sources:

Photos Taken: _____

<input type="checkbox"/> RBDMS	<input type="checkbox"/> KGS	<input type="checkbox"/> TA Program
<input type="checkbox"/> T-I Database	<input type="checkbox"/> District Files	<input type="checkbox"/> Courthouse
<input type="checkbox"/> Other: _____		

By: Ken Jehlik

ECRS

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

RECEIVED
APR 10 2018
KCC DODGE CITY

NP
SA

Form: 02/22/2008