

KCC OIL/GAS REGULATORY OFFICES

Date: 08/28/18

District: 01

Case #: _____

☒ New Situation

☐ Response to Request

☐ Follow-Up

☐ Lease Inspection

☐ Complaint

☒ Field Report

Operator License No: 4767

API Well Number: 15-203-20340-00-00

Op Name: Ritchie Exploration Inc

Spot: SE SW Sec 3 Twp 17 S Rng 37 ☐ E / ☒ W

Address 1: PO Box 783188

728 Feet from ☐ N / ☒ S Line of Section

Address 2: 8100 E 22nd St N. #700

1973 Feet from ☒ E / ☐ W Line of Section

City: Wichita

GPS: Lat: _____ Long: _____ Date: _____

State: Kansas Zip Code: 67226

Lease Name: Lewis Trust 3 C Well #: 1

Operator Phone #: 316 691 9500

County: Wichita

Reason for Investigation:

Alt II cementing

Problem:

None

Persons Contacted:

None

Findings:

8 5/8 @ 220', 5 1/2 @ 4966' w/ 235 sx, Port Collar @ 2449', TD @ 4980'.
Consolidated pumped 300 sx cmt & lost circulation. Shut down for 35 minutes, then resume pumping at 1 bpm & regained circulation.
Pumped a total of 450 sx 60/40 poz, 8% gel with 500 # hulls.
Circulated 40 sx to the pit.

Action/Recommendations:

Follow Up Required ☐ Yes ☐ No ☒

Date: _____

Alternate II cementing complete

Verification Sources:

Photos Taken: _____

| | | |
|---------------------------------------|---|-------------------------------------|
| <input type="checkbox"/> RBDMS | <input type="checkbox"/> KGS | <input type="checkbox"/> TA Program |
| <input type="checkbox"/> T-I Database | <input type="checkbox"/> District Files | <input type="checkbox"/> Courthouse |
| <input type="checkbox"/> Other: _____ | | |

By: Ken Jehlik

ECRS

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

RECEIVED
SEP - 4 2018
KCC DODGE CITY

Form: 02/22/2008