

3-4-68
copy of WPR
Shallow water

15-073-01786-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner Bodock Oil Co. Address Box 752, Winfield, Kansas
(Applicant)

Lease (Farm Name) DeMalorie Sowders Well No. 23

Well Location SE SE SW Sec. 1 Twp. 22 Rge. 10 (E)-~~W~~

County Greenwood Field Name (if any) _____

Total Depth 2037' Oil ~~Gas XXXXXX Dry Hole~~

Was well log filed with application? Yes . If not, explain: _____

Date and hour plugging is desired to begin April 19, 1954 10:00 AM

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.

(Use an additional sheet if necessary) _____

Name of the person on the lease in charge of well for owner Bodock Oil Co.

C/O H.H. Fischer Address Box 752, Winfield, Kansas

Name of Plugging Contractor Janison Brothers Permit # 24

Address Madison Kansas

Invoice covering assessment for plugging this well should be sent to _____

Bodock Oil Co. Address Box 752, Winfield, Kansas

and payment will be guaranteed by applicant.

RECEIVED REGISTRATION COMMISSION STATE CORP. COMMISSION

MAR 13 1954

MAR 15 1954

Med M. Pettit

Med M. Pettit

Applicant or Acting Agent

Date 12 March 1954

PLUGGING

FILE SEC 1 T 22 R 10E
BOOK PAGE 20 LINE 32

CONSERVATION DIVISION CONSERVATION DIVISION
Kansas
Wichita, Kansas



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

March 18, 1954.

Well No. 23
Lease D. Sowders
Description SE 08 SW 1-22-10E
County Greenwood
File No. 28-32

Bodock Oil Co.
Box 752
Winfield, Kans.

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. A. W. Hartscock, Box 524, Eureka, Kans.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: District Plugging Supervisor

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 20-32

LOCATION SE SE SW

SEC. 1 TWP. 22 RGE. 10E

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 23 Lease D. Sowders

Operator Bodock Oil Co; Address Box 752 Winfield, Kansas

Field _____ County Greenwood

Total Depth 2037' Feet.

Plugging Contractor Jamison Brothers

Plugging Contractor's License No. 24

Address _____ Madison, Kansas

(Describe briefly the manner in which the well was plugged)

Mud & rock from 2037' to 1938, cemented with 2 sacks
set plug at 988' six foot rock, cemented with 12 sacks,
set plug at 300' 10' rock and cemented with 20 sacks,
mud and rock to 20' cemented with five sacks, covered with
soil.

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 - 1954

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 1 TWP. 22 RGE. 10E
BOOK PAGE 20 LINE 32

A. W. Hartsock
District Conservation Agent

Date April 28, 1954

Lease: Demslorie Sowders

Well # 23

SE SE SW Sec. 1 T22 R10E, Greenwood County, Kansas

Surface Elev: 1192'

Date Completed: March 20 1926

Casing record:

10" 1105'
 8 1/2" 1505'
 6 5/8" 1980'

Bartlesville Sand: Top 1980

Base 2037

T.D. 2037

Formation:

Shale	35	Lime	755
lime	40	shale	760
shale	130	lime	780
lime	140	shale	940
shale	150	lime	945
lime	160	Shale sandy	1020
shale	175	sand	1070
lime	180	lime	1075
shale	340	shale	1090
lime	350	lime	1115
shale	360	shale	1120
lime	365	lime	1125
shale	405	shale	1130
lime	410	lime	1200
shale	430	shale	1280
lime	450	lime	1285
shale	470	shale	1325
lime	475	lime	1365
shale sandy	490	shale	1370
shale	510	lime	1450
lime	530	lime sandy	1460
shale	545	lime	1510
lime	550	shale	1520
shale	570	lime	1625
lime	575	shale	1645
shale	580	lime	1660
lime	590	shale	1730
shale	605	lime	1740
lime	620	shale	1760
shale	640	lime	1770
lime	655	shale	1775
shale	660	lime	1785
lime	665	shale	1980
shale	700	oil sand.	2037


RECEIVED
 STATE CORP. COMMISSION
 MAR 15 1954
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. L T 22 R 10E
 BOOK PAGE 20 LINE 32

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Greenwood County, Sec. 1 Twp. 22 Rge. 10 (E) E (W)
Location as "NE/CNW&SW" or footage from lines SE SE SW
Lease Owner Bodock Oil Co. (Phillips Pet. Co.)
Lease Name D. Sowders Well No. 23
Office Address Box 752, Winfield, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 20, 1926 19
Application for plugging filed March 18, 1954 19
Application for plugging approved March 18, 1954 19
Plugging commenced ~~April 30, 1954~~ April 12 19
Plugging completed April 30, 1954 19
Reason for abandonment of well or producing formation
Oil exhausted
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A.W. Hartsook
Producing formation Mississippi Lime Depth to top 1980 Bottom 2037 Total Depth of Well 2037 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	1105	1105
				8"	1505	1019
				7"	1980	1777

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 2 sacks of cement on Packer at 1938 feet. Top of cement 1924.
Pushed plug 988 feet. six feet of rock to 982 feet. Dumped 12 sacks of cement
Top of cement 962 feet Set Bridge at 300 feet. Dumped 20 sacks of cement
at 285 feet. Mud and rock to 10 feet. Dumped 5 sacks of cement into
cellar 4 feet. Filled cellar in with mud and rock.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Jamison Bros Hydraulic casing pullers
Address Madison, Kansas

STATE OF Kansas COUNTY OF Cowley, ss.
A. W. Hartsook (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Bodock Oil Co
Winfield Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28 day of May, 1954

My commission expires 8-2-55 Donald D. Dutcher Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1954
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 1 T 22 R 10 E
PAGE 20 LINE 32