

1 020026

24 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,044 - 0000

NW NE, SEC. 31, T 20 S, R 25 W X

4520 feet from S section line

1880 feet from E section line

Lease Name Slagle Well # 3

County Ness 149.57

Well Total Depth 4602 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

TECHNICIAN'S PLUGGING REPORT

Operator License # 4655

Operator: BHP Petroleum (Americas) Inc.  
Name & Address  
925 Patton Road  
Great Bend, KS 67530

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 KS State Bank Bldg., Wichita, KS, 67202

Company to plug at: Hour: 11:30 a.m. Day: 6 Month: 9 Year: 19 86

Plugging proposal received from Walter Hooten

(company name) Red Tiger Drilling (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2386 KB Anhydrite 1600

1st plug at 1600' with 50 sx cement

2nd plug at 800' with 50 sx cement

3rd plug at 250' with 40 sx cement

4th plug at 0-10' with 10 sx cement

5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Don Ubel

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:45 p.m. Day: 6 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1620' with 50 sx cement

2nd plug at 860' with 50 sx cement

3rd plug at 250' with 40 sx cement

4th plug at 0-40' with 15 sx cement

5th plug to circulate rathole with 10 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

Signed *Steven R. Barlow* (TECHNICIAN)

DATE 9-11-86

SEP 10 1986

INV. NO. 14919 9-6