

1 090462

8-25

API NUMBER 15-135-22,990-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW SW, SEC. 32, T 20 S, R 25 W
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030

Lease Name Doebbeling A Well # 1

Operator: Vess Oil Corporation

County Ness 145.93

Name & Address 8100 E. 22nd St. N, Bldg. 300

Well Total Depth 4490 feet

Wichita, KS 67226

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 601

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address Rt. 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 25 Month: 8 Year: 1994

Plugging proposal received from Mike Kasselmann

(company name) Vess Oil Corporation (phone) 316-793-3051

Work: 5 1/2" at 4488' w/150 sx cement. Perfs at 4370-74', DV tool @1586' cemented w/350 sx cmt.

1st plug pump 300 lbs. hulls and cement to 4370'.

Check backside.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 25 Month: 8 Year: 1994

ACTUAL PLUGGING REPORT 1st plug pumped 3 sxs. hulls with 250 sx cement down 5 1/2" casing.

Maximum pressure 800 psi and shut in 500 psi.

Backside would not take.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 12 1994
INV. NO. 41200

observe this plugging.

Signed [Signature] (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1994
CONSERVATION DIVISION
WICHITA, KANSAS