

To: 1 120550
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-8
API NUMBER 19- 165-21,462-0000 217 R

NW SW SE, SEC. 29, T 17 S, R 16 W/E

990 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Lease Name Rothe "C" Well # 1

Operator: A F G Energy, Inc.

County Rush 116-35

Name & Address P.O. Box 605

Well Total Depth 3580 feet

Russell, KS 67665

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 8 Month: 4 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 3579' w/175 sx cement, PBD 3526', Perfs at 3020-3508' (5 sets)

1st plug sand back to 2970' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release

8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 8 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 50 sx cement and pushed

plug to 2867' in 4 1/2" casing,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Pumping pressure 0-600 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2019' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

PLEASE OBSERVE THIS PLUGGING.

DATE 4-22-91

APR 16 1991

Signed Steve Pfeifer
(TECHNICIAN)

INV. NO. 31613

CONSERVATION DIVISION
WICHITA, KANSAS

FORM CP-2/3
Rev. 01-84