

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-091-19213-0000
 Spot: SENWSE Sec 32 Twp 13 S Rng 23 E / W
1724 Feet from N / S Line of Section
1501 Feet from E / W Line of Section
 GPS: Lat: 38.873790 Long: 94.876930 Date: 5/8/12
 Lease Name: Rothfelder Well #: ISH 01
 County: Johnson Total Vertical Depth: 690 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>SURF - Casing</u>	<u>8.000</u>	<u>20</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. MARKET</u>	<u>PROD - Casing</u>	<u>2.000</u>	<u>690</u>	<u>0</u>	
Address 2: _____	_____	_____	_____	_____	_____
City: <u>WICHITA</u>	_____	_____	_____	_____	_____
State: <u>KS</u> Zip Code: <u>67202</u> - _____	_____	_____	_____	_____	_____

Well Type: OG - Oil & Gas UIC Docket No.: _____ Date/Time to Plug: 8/17/12 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Nick Kepley Company Name: KWS Phone: (620) 431-8945

Pump portland cement from TD to surface.

Proposed
Plugging
Report:

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 8/17/12 / _____ KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Hook onto 1" and try to pull out. Stuck in well. Left strain on 1". Finally pulled loose. Pull 1" out. Pull total of 690 ft out. Perforate well at 375 ft and 75 ft. Run 1" to TD. Pump portland cement to surface. Wash 1" outside 2" to 70 ft. Pump portland cement to surface. Pull pipe and top off well. Pump total of 42 sacks of cement. Well plugged.		<u>75</u>	<u>375</u>	

KANSAS CORPORATION COMMISSIC:
 OCT 02 2012
 RECEIVED

Remarks: Contract No. 11782. Control No. 20130012-001. GPS NAD 83. Irreg. Sec. by Taylor Herman.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03

Frank Guilfoyle
 (Technician)