

1 06005  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-6  
API NUMBER 15- 135-23,542 -0000  
E/2 NW SW, SEC. 35, T 20 S, R 25 W/4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030

Operator: Vess Oil Corporation  
Name & Address: 8100 E. 22nd St. N, Bldg. 300  
Wichita, KS 67226

1980 feet from S section line  
4290 feet from E section line

Lease Name Almquist BK Well # 1

County Ness 145.92

Well Total Depth 4490 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 753

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company Inc. License Number 5929

Address 310 W. Central, #117, Wichita, KS 67202

Company to plug at: Hour: 3:20 p.m. Day: 6 Month: 1 Year: 19 91

Plugging proposal received from Jay

(company name) Duke Drilling Company Inc. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1671-1716'  
1st plug at 1725' with 50 sx cement, 2nd plug at 900' with 50 sx cement,  
3rd plug at 475' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:45 p.m. Day: 6 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1725' with 50 sx cement,  
2nd plug at 900' with 50 sx cement,  
3rd plug at 475' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 8 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DATE FEB 14 1991  
WV. NO. 30745

Signed [Signature] (TECHNICIAN)

EFFECTIVE DATE: 12-10-90

FORM MUST BE TYPED  
FORM C-1 4/90

"CORRECTED LOCATION" *Correction*

State of Kansas

NOTICE OF INTENTION TO DRILL 135-23,542-0000 ALL BLANKS MUST BE FILLED  
Must be approved by the K.C.C. five (5) days prior to commencing well

FORM MUST BE SIGNED

Expected Spud Date December 15 1990  
month day year

\* C E/2 NW SW Sec 35 Twp 20 S, Rg .25 East West

OPERATOR: License # 5030  
Name: Vess Oil Corporation  
Address: 8100 E. 22nd St. N., Bldg. 300  
City/State/Zip: Wichita, KS 67226  
Contact Person: Bill Horigan  
Phone: 316-682-1537

\* 1980 feet from South line of Section  
4290' feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5929  
Name: Duke Drilling Co., Inc.

County: Ness  
Lease Name: Almquist BK Well #: 1  
Field Name: Almquist Ext.  
Is this a Prorated Field? yes XX no  
Target Formation(s): Mississippi  
Nearest lease or unit boundary: 660  
Ground Surface Elevation: 2395 (E) feet MSL  
Domestic well within 330 feet: yes XX no  
Municipal well within one mile: yes XX no  
Depth to bottom of fresh water: 300  
Depth to bottom of usable water: 700  
Surface Pipe by Alternate: XX  
Length of Surface Pipe Planned to be set: 720  
Length of Conductor pipe required: N/A  
Projected Total Depth: 4450  
Formation at Total Depth: Mississippi  
Water Source for Drilling Operations:

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Inj ... Infield  Mud Rotary  
... Gas ... Storage  Pool Ext. ... Air Rotary  
... OWWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

If OWWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_

*542*  
Pusher AV  
SPUD DATE 12-27-90 INIT. Sn  
LENGTH SURFACE PLANNED 720  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 2 1/2 @ 723 CONDUCTOR  
ANHYDRITE T- 1671 B- 1716 ELEVATION  
TD 4490 FORMATION MISS.  
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N  
Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ Ft. W/ SX  
Anhydrite Base @ 1725 Ft. W/ 50 SX  
1/2 Base Anhyd. @ 900 Ft. W/ 50 SX  
1/2, 1/2 Plug @ 475 Ft. W/ 50 SX  
Bottom Surface @ Ft. W/ SX  
40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 1 1/2 SX MOUSE HOLE W/ — SX  
WATER WELL SX (Irr. Well — Pond —)  
TECHNICIAN CM DATE 1-2-91 Hauling  
TYPE OF CEMENT 60/40 P.c.e 670 1/4" flow seal  
STARTING TIME 3:20 (AM/PM) DATE 1-6-90  
COMPLETION TIME 5:45 (AM/PM) DATE 1-6-90  
CEMENT COMPANY alled.