

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20289-00-00
Spot: SENWSW Sec/Twnshp/Rge: 36-29S-25W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: CHRISTIAN CHURCH Well Number: 1-A
County: FORD Total Vertical Depth: 5430 feet

Operator License No.: 5123 Conductor Pipe: Size _____ feet:
Operator Name: PICKRELL DRILLING COMPANY Surface Casing: Size 8.625 feet: 498 WITH 275 SX CMT
Address: 100 SOUTH MAIN - SUITE 505 Production: Size 4.5 feet: 5419 WITH 150 SX CMT
WICHITA, KS 67202 Liner: Size _____ feet: _____ 176.48

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/16/2000 2:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: TONY DUMLER Company: PICKRELL DRILLING Phone: (316) 262-8427

Proposed Plugging Method: SAND TO 5200' WITH 4 SX CMT. 1ST PLUG AT 1600' WITH 50 SX CMT. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR GE SPACER.

Plugging Proposal Received By: STEVE MIDDLETON

Witness Type: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 11/16/2000 5:00 PM

KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PERFS AT 5259'. SAND TO 5200' WITH 4 SX CMT ON TOP. 1ST PLUG PULL CASING TO 1600' & PUMP 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 540' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 15 SX CMT. CIRCULATE CEMENT TO SURFACE.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 2000

CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2630' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

INVOICED

DATE 11/28/00

NOV 20 2000

INV. NO. 2001061019

MP

CR-2/3