

To: 1051869 11-30
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057-20,382 0000
NW SW SW, SEC. 36, T 29 S, R 25 W/E
990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152
Operator: Lee Banks DBA Banks Oil Company
Name & Address: 200 W. Douglas, Ste. 550
Wichita, KS 67202

Lease Name Shelor Well # 1-36
County Ford 175.50
Well Total Depth 5400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 597

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Peters Drilling Co., Inc. License Number 3400
Address P.O. Box 742, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 30 Month: 11 Year: 19 94

Plugging proposal received from Mike Peters
(company name) Peters Drilling Co., Inc. (phone) 316-793-6721

Core: 4 1/2" at 5400' w/150 sx cement, PBD 5325', Perfs at 5262-68, 5335-41'
1st plug sand back to 5200' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:50 p.m. Day: 30 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 5200' and dumped 4 sx cement on top of
sand through bailer,
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100' released
8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 600 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2150' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 12-6-94
INV. NO. 41814

Signed Richard W. Lacy
(TECHNICIAN)

KANSAS RECEIVED
CORPORATION COMMISSION
DEC 02 1994
CONSERVATION DIVISION
WICHITA, KS