

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-10260-00-00  
Spot: CNENW Sec/Twnshp/Rge: 12-22S-23W  
660 feet from N Section Line, 1980 feet from W Section Line  
Lease/Unit Name: DAN EWY A Well Number: 2  
County: HODGEMAN Total Vertical Depth: 4567 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: 100 N. BROADWAY, STE. 970  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 240 WITH 200 SX CMT  
Production: Size 7 feet: 4545 WITH 150 SX CMT  
Liner: Size \_\_\_\_\_ feet: 148.43

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/14/2001 1:45 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO Phone: (785) 628-6101

Proposed Plugging Method: PUMP 80 SX CMT & 500# HULLS ON BOTTOM. PRESSURE TEST. PERFORATE AT 600'. PUMP 175 SX CMT. TIE ONTO BACKSIDE AND PUMP 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/14/2001 4:15 PM KCC Agent: MICHAEL MAIER

**Actual Plugging Report:**

PUMP 80 SX CMT & 500# HULLS TO BOTTOM. PRESSURED TO 1500# AND HELD. PERFORATE AT 600'. INJECTION RATE OF 3 BBL PER MINUTE AT 1100#. MIXED 175 SX CMT AND DID NOT CIRCULATE. MAXIMUM PRESSURE 1400#. SHUT IN WITH 400#. TIED ONTO BACKSIDE AND MIXED 20 SX CMT. PRESSURED TO 500# AND HELD.

**INVOICED**

DATE 6-27-01

INV. NO. 2001062001

RECEIVED

KANSAS CORPORATION COMMISSION

JUN 27 2001

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

CONSERVATION DIVISION

Plugged through: CSG

District: 01

Signed

Michael Maier  
(TECHNICIAN)

[Signature]  
Form CP-2/3

JUN 22 2001

MD