

1 080074

7-17

API NUMBER 15- 151-21,998 0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 NW NW, SEC. 5, T 29 S, R 12 W EX

4290 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Riffey Well # 1

Operator: Falcon Exploration Inc.

County Pratt 153.11

Name & Address

125 N. Market, #1075

Well Total Depth 4711 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 5 p.m. Day: 16 Month: 7 Year: 19 90

Plugging proposal received from Craig Christopher

(company name) Allen Drilling Company (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at Arbuckle with 50 sx cement, 2nd plug at 750' with 75 sx cement,

3rd plug at 360' with 75 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 a.m. Day: 17 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 4655' with 40 sx cement,

2nd plug at 750' with 75 sx cement,

3rd plug at 360' with 75 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUL 25 1990

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.

(If additional description is necessary, use BACK of this form.)

INVOICED did not observe this plugging.

DATE: 7-30-90

INV. NO. 28815

Signed Mike Spain (TECHNICIAN)

EFFECTIVE DATE: 7-7-90

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas
NOTICE OF INTENTION TO DRILL

151-21,998 0000

FORM MUST BE SIGNED
ALL SPACES MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 7 5 90
month day year

S/2 NW NW Sec 5 Twp 29 S, Rg 12 East West

OPERATOR: License # 5316
Name: Falcon Exploration Inc.
Address: #1075 125 N. Market
City/State/Zip: Wichita, KS 67202
Contact Person: Jim Thatcher
Phone: (316) 265-3351

4290 feet from South line of Section
4620 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5418
Name: Allen Drilling

County: Pratt
Lease Name: Riffey Well #: 1
Field Name: Wildcat
Is this a Prorated Field? yes no
Target Formation(s): Mississippi, Viola, Arbuckle

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 O/W/O Disposal Wildcat Cable
 Seismic; # of Holes

Nearest lease or unit boundary: .660
Ground Surface Elevation: Unknown 290 feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water: 210
Depth to bottom of usable water: 240
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 320
Length of Conductor pipe required: None
Projected Total Depth: 4600
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
 well farm pond other

If O/W/O: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes no
If yes, total depth location: _____

DWR Permit #: _____
Will Cores Be Taken?: yes no
If yes, proposed zone: _____

Exp. 1/2/91

AFFIDAVIT 260' Alt. I Req. SPUR 7-6-90 320'-8 3/8"

Pusher Craig Christopher
SPUD DATE 7-6-90 INIT. mlw

LENGTH SURFACE PLANNED 720' 8 5/8"
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbbs. when done bbbs.

RATHOLE AHEAD? YES N SIZE HOLE 12 3/4" to 1000
SURFACE PIPE 278 @ 330 CONDUCTOR
ANHYDRITE T- B- ELEVATION 290

TD 4711 FORMATION (Arbuckle)

RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____
SX _____ SX Y N

Arbuckle Plug @ 4455 Ft. W/ 40 SX

Hug./Council @ _____ Ft. W/ _____ SX

Anhydrite Base @ +750 Ft. W/ 75 SX

1/2 Base Anhy. @ _____ Ft. W/ _____ SX

1/2, 1/2 Plug @ _____ Ft. W/ _____ SX

Bottom Surface @ 360 Ft. W/ 75 SX

40' Plug @ 40-0 Ft. W/ 10 SX

RAT HOLE CIRCUIT 15 SX MOUSE HOLE W/ _____ SX

WATER WELL _____ SX (Irr. Well _____ Pond _____)
Hauling _____

TECHNICIAN MS DATE 7-13-90

TYPE OF CEMENT 60/40 670 gell

STARTING TIME 5:15 (AM/PM) DATE 7-16-90

COMPLETION TIME 1:30 (AM/PM) DATE 7-17-90

CEMENT COMPANY Arbuckle