

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

7-27

2-020090

API Number: 15-035-20,545-0000

NW NE NW SECTION 26 TWP 33 RANGE 05E

OPERATOR LICENSE # 5141
OPERATOR ZENITH DRILLING CORPORATION
NAME & P.O. BOX 780428
ADDRESS WICHITA, KS 67278

~~4954628~~ FEET FROM S SECTION LINE
~~33003630~~ FEET FROM E SECTION LINE

LEASE NAME MILLER "B" #1
COUNTY COWLEY
WELL TOTAL DEPTH 3023' 98.25
PIPE
SURFACE CASING 8 5/8" @238

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE, INC.

ADDRESS: P.O. BOX 467, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 11:30 DAY: 27 MONTH: 7 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: RUSSELL BRIGGS

COMPANY NAME: ZENITH DRILLING CORP. PHONE: (316) 684-9777

WERE: SAND BACK 50' ABOVE OPEN HOLE WITH 5 SX CEMENT ON TOP OF SAND. SHOOT AND PULL CASING TO SURFACE. RUN 1" TUBING TO 288' AND CIRCULATE CEMENT TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY: DISTRICT 2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 12:00 DAY: 27 MONTH: 7 YEAR: 1998

ACTUAL PLUGGING REPORT: SAND BACK TO 2950' WITH 5 SX CEMENT ON TOP OF SAND. SHOOT AND PULL CASING AT 1600' AND PULL TO SURFACE. RUN 1" TUBING TO 288' AND CIRCULATE 90 SX COMMON CEMENT WITH 4% GEL TO SURFACE.

RECEIVED
KANSAS CORPORATION COMMISSION

REMARKS: ELMORE'S #2592

AUG 24 1998
8-24-98
CONSERVATION DIVISION
WICHITA, KS

I DID NOT OBSERVE THIS PLUGGING.


DONALD KOBERECHT

INVOICED
AUG 24 1998

DATE _____
INV. NO. 51206

FORM CP-2/3
REV. 3/90