

To: 1 040788
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-27

API NUMBER 15- 151-21,998-A 0001

S/2 NW NW, SEC. 5, T. 29 S, R. 12 W/28X

4290 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9854

Lease Name Riffey Well # 1

Operator Name Marmac Petroleum Co.

County Pratt

Address 2120 S. Holly, Ste. 207

Well Total Depth 4708 153.01 feet

Denver, CO 80222

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hardtner Well Service License Number 30607

Address 150 N. Main, Ste. 1026, Wichita, KS 67202

Company to plug at: Hour: 11:15 a.m. Day: 27 Month: 9 Year: 19 93

Plugging proposal received from Sam Flyingout

(company name) Hardtner Well Service (phone) 316-269-9052

were: 5 1/2" at 4708' w/200 sx cement, PBDT 4674', Perfs at 4423-30'

1st plug sand back to 4370' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 27 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4375' and put 2 sx cement on top through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 200 psi and shut in 175 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2626' of 5 1/2" casing. Additional description is necessary, use BACK of this form.

I (did / ~~did not~~) observe this plugging.

DATE 10-7-93

Signed Stephen J. Pfeifer (TECHNICIAN)

DIV. NO. 38902

9-27 DEC 30 1993 MAR 15 1994

RECEIVED STATE CORPORATION COM. OCT 06 1993 CONSERVATION DIVISION Wichita, Kansas