

TO: 1100295
STATE CORPORATION COMMISSION

5-04

API NUMBER 15-033-21,008
200'W N/2 NE SEC. 25, T 33 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1520 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME TODD WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY COMANCHE 149.88

OPERATOR LICENSE # 31691

WELL TOTAL DEPTH 6150 FEET

OPERATOR: CORAL COAST PETROLEUM, LLC PRODUCTION CSG: SIZE " FEET

NAME AND ADDRESS 200 E 1ST #001 WICHITA, KS 67202 SURFACE CASING: SIZE 8 5/8" @ 625' WITH SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DUKE DRILLING LICENSE NUMBER 5929

ADDRESS 100 S MAIN, SUITE 410, WICHITA, KS 67202-3737

COMPANY TO PLUG AT: HOUR: 10:45 AM DAY: 04 MONTH: 05 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM KEN MCGUIRE

(COMPANY NAME) DUKE DRILLING (PHONE) 316-267-1331

WERE:

1ST PLUG AT 900' WITH 50 SX CEMENT. 2ND PLUG AT 620' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT.

4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 04 MONTH: 05 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 900' WITH 50 SX CEMENT.

2ND PLUG AT 620' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT.

4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

RECEIVED

I DID NOT OBSERVE THIS PLUGGING.

SIGNED

Gary Winters
(TECHNICIAN)

FORM CP-2/3

DATE 5-25-99

MAY 21 1999

INV. NO. 60981

05-21-99

54 AUG 03 1999
CONSERVATION DIVISION
Wichita, Kansas