

1052002

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

1-9-96

API NUMBER 15- 187-20,807 0000
NE SW, SEC. 3, T 27 S, R 41 W/E
1980 feet from S section line
3300 feet from E section line
Lease Name Floyd Well # 1-3
County Stanton 175.18
Well Total Depth 5390 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1755

TECHNICIAN'S PLUGGING REPORT
Operator License # 5030
Operator: Vess Oil Corporation
Name
Address 8100 E. 22nd St. N, Bldg. 300
Wichita, KS 67226

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418
Address P.O. Box 1389, Great Bend, KS 67530-1389

Company to plug at: Hour: 11:30 a.m. Day: 9 Month: 1 Year: 19 96

Plugging proposal received from Richard
(company name) Allen Drilling Company (phone) 316-793-5681

work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 3007' with 100 sx cement, 2nd plug at 1790' with 50 sx cement,
3rd plug at 800' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION
01-16-96
1996

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 p.m. Day: 9 Month: 1 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 3007' with 100 sx cement,
2nd plug at 1790' with 50 sx cement,
3rd plug at 800' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)
I (XXX) do hereby certify this plugging.

INVOICED
DATE JAN 23 1996

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 44702
1-9

EFFECTIVE DATE: 12-18-95

State of Kansas

NOTICE OF INTENTION TO DRILL 187-20,807

Must be approved by the K.C.C. five (5) days prior to commencing well

DISTRICT # 1
SEAT Yes No

Expected Spud Date Dec. 18 1995
month day year

Spot NE SW Sec 3 Twp 27 S, Rg 41XX East West

OPERATOR: License # 5030
Name: Vess Oil Corporation
Address: 8100 E. 22nd Street N. Bldg. 300
City/State/Zip: Wichita, KS 67226
Contact Person: W. R. Horgan
Phone: 316-682-1537

1980 feet from South North line of Section
3300 feet from East West line of Section

IS SECTION XX REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 5418
Name: Allen Drilling Company

County: Stanton

Lease Name: Floyd Well #: 1-3

Field Name: W/C

* Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Morrow/Miss

Nearest Lease or unit boundary: 660'

Ground Surface Elevation: 3288' feet MSL

Water well within one-quarter mile: XX yes no

Public water supply well within one mile: yes XX no

Depth to bottom of fresh water: 200'

Depth to bottom of usable water: 720'

Surface Pipe by Alternate: XX 1 2

Length of Surface Pipe Planned to be set: 1750'

Length of Conductor pipe required: 0

Projected Total Depth: 5450'

Formation at Total Depth: Miss

Water Source for Drilling Operations: XX well farm pond other

DWR Permit #: N/A

Will Cores Be Taken? yes no

If yes, proposed zone: 740' Alt. I Req.

Well Drilled For: Well Class: Type Equipment:

XX Oil ... Enh Rec ... Infield XX Mud Rotary

... Gas ... Storage ... Pool Ext. ... Air Rotary

... OWWO ... Disposal XX Wildcat ... Cable

... Seismic; ... # of Holes ... Other

... Other

If OWWO, old well information as follows:

Operator:

Well Name:

Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes XX no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 6/13/96

APPENDIX I

* PRORATED & SPACED IN CHASE

Pusher Richard

SPUD DATE 12-21-95 INIT. YMLW

LENGTH SURFACE PLANNED 1750'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

BATHOED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/2" @ 1755 CONDUCTOR
ANHYDRITE T- B- ELEVATION

TD 5390 FORMATION

IRAN PIPE @ DV TOOL ALT II DONE
@ SX SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ 5300' Ft. W/ 100 SX

Anhydrite Base @ 1790 Ft. W/ 90 SX

1/2 Base Anyh. @ 800 Ft. W/ 40 SX

1/2, 1/2 Plug @ 400 Ft. W/ SX

Bottom Surface @ 400 Ft. W/ SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE/W/ SX

WATER WELL SX (Irr. Well Pond
Hauling

TECHNICIAN A.L. DATE 12-29-95

TYPE OF CEMENT 60/40 60/90

STARTING TIME 4:30 (AM/PM) DATE 1-9-96

COMPLETION TIME 4:30 (AM/PM) DATE 1-9-96

CEMENT COMPANY PKL