

1030352

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,748-00-00

SW SW SW , SEC. 3 , T 19 S, R 26 W/E
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Lease Name Adolph Well # 1

Operator: DaMar Resources, Inc.

County Ness 149.21

Name & Address P. O. Box 70

Well Total Depth 4591 feet

Hays, KS 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Box 506, Russell, KS 67665

Company to plug at: Hour: 2:00 am Day: 2 Month: January Year: 19 85

Plugging proposal received from Gary Flax

(company name) Emphasis (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1920' with 70 sx cement

2nd plug at 900' with 50 sx cement

3rd plug at 300' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:15 am Day: 2 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1920' with 70 sx cement, 2nd plug at 900' with 50

sx cement, 3rd plug at 300' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 09 1985
01-09-1985
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 1-15-85

Signed Steve Durrant (TECHNICIAN)

INV. NO. 6449