

1 080272

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,730

SE NW NE, SEC. 32, T 28 S, R 18 W/E

4290 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9726

Lease Name Loewen Well # 1

Operator: Gross Petroleum Management, Inc.
Name & Address 900 Building of the Southwest
Midland, TX 79701

County Kiowa 160.81

Well Total Depth 4948 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 611

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 4:30 pm Day: 30 Month: November Year: 19 84

Plugging proposal received from Charles Merideth

(company name) Wheatstate (phone) 316-672-7514

were: 5 1/2" set at 4935' Perfs at 4935-4948' CIBP set at 4880'

1st plug set CIBP at 4880' with 4 sx cement

2nd plug at 1200' with 40 sx cement *Spot plugs through casing w/ heavy mud in*

3rd plug at 660' with 40 sx cement *hole*
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:45 pm Day: 30 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4935' Perfs at 4935-4948'

1st plug set CIBP at 4880' with 4 sx cement, 2nd plug at 1200' with 40 sx cement, 3rd
plug at 660' with 40 sx cement, 4th & 5th plugs - solid bridge- hulls - plug at 40' --

cement to surface with 10 sx cement. *Spot plugs through casing w/ heavy*
mud in the hole.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Recovered 2500' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3%cc

(If additional description is necessary, use BACK of this form.)

observe this plugging.

DEC 05 1984

CONSERVATION DIVISION
Wichita, Kansas

Signed J. H. Metz
(TECHNICIAN)

INVOICED

DATE 12-12-84

INV. NO. 5952