

1060833

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,622 0000  
60' N of C  
SE NW SE, SEC. 32, T 28 S, R 18 W/E  
1710 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9726

Lease Name Dirks Well # 1

Operator: Gruss Petroleum Management, Inc.  
Name & Address: 900 Building of the Southwest  
310 West Texas  
Midland, TX 79701

County: Kiowa 160.55  
Well Total Depth 4940 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 595

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pulling License Number 6497

Address P. O. Box F, Sublette, KS 67877

Company to plug at: Hour: 10:00 am Day: 13 Month: March Year: 19 86

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 4924' PBTD 3658' Perfs at 3593-3598 Pump through 4 1/2" with mud between  
1st plug pump 2 sx hulls and 20 sx cement to cover perfs. <sup>plugs</sup>

2nd plug pump 5 sx gel and 50 sx cement at 1200'

3rd plug at 625' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:00 pm Day: 13 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to 3510', 2nd plug at

1200' with 5 sx gel and 50 sx cement, 3rd plug at 625' with 40 sx cement, 4th & 5th plugs

solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Recovered 2447' 4 1/2" casing. Used common cement by Midwest.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 20 1986

INV. NO. 13022

3-13

MAR 20 1986

CONSERVATION DIVISION  
Wichita, Kansas

Signed Paul A. Luthi  
(TECHNICIAN)