

4-110078

D-25,648

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-21,789-0000

NW SW SE /4 SEC. 08, 14 S, 19 W  
990 feet from S section line  
2310 feet from E section line

Operator license# 100 *10*

Lease: Kinderknecht Well # *11B* B-11

Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13<sup>th</sup> Street  
Hays, Kansas 67601  
Control #20000026-002

County: Ellis  
Well total depth 3950 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 325 feet

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Kansas Corporation Commission License# 100

Address: 2301 E. 13<sup>th</sup> Street - Hays, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 31 Month: December Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 3 785-625-0550

Were: Plug according to KCC Rules & Regulations.  
Area is near an existing sink hole and casing is thought to be parted at  
Approximately the Cedar Hill Formation.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ X ], None [ ]

Completed: Hour: 11:30 A.M., Day: 6, Month: January, Year: 2000

Actual plugging report: 8 5/8" S.P. set at 325' w/175 sxs cmt. 4 1/2" casing at 3832' w/250 sxs. At 1485' to surface with 700 sxs cement. Squeezed at 3900' with unknown amount of cement. Hit bridge's at 800' to 1235'. Casing bad at various intervals. 12/31/99 - tubing to 1235' and circulated 120 sxs Class A cement with 2% c.c. Tied to 8 5/8" x 4 1/2" annulus and pumped 30 sxs Class A with 2% c.c. to Max. P.S.I. 200#. S.I.P. 150#. Tied to 4 1/2" casing - pumped 120 sxs 60/40 pozmix with 10% gel and 450# hulls to Max. P.S.I. 400#. Went on vacumn. Shut down 1 1/2 hrs. 4 1/2" pumped 30 sxs 60/40 pozmix with 10% gel and 250# hulls - went on vacumn. 01/06/00 4 1/2" casing pumped 30 sxs 60/40 pozmix - 10% gel and 100# hulls to Max. P.S.I. 500#. S.I.P. 500#. Total 150 sxs Class A, 180 sxs 60/40 pozmix with 800# hulls.

Remarks: Allied Cementing. Werth Tank Service - water.

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING X, CASING X. Elevation: 2195 GL

I did [ X ] / did not [ ] observe the plugging.

*Roger L. Mases*  
Agent  
STATE CORPORATION COMMISSION  
Form EP 2/3

JAN 31 2000  
1-31-00  
CONSERVATION DIVISION  
Wichita, Kansas

FRONTIER OIL COMPANY  
1720 KANSAS STATE BANK BLDG  
WICHITA, KS 67202

REPLACEMENT CARD  
#11 "B" KINDERKNECHT

8-14-19W  
NW SW SE

CONTR RED TIGER DRILLING CO CTY ELLIS

GEOL RICHARD D PARKER FIELD KRAUS

E 2200 KB CM 10/2/79 <sup>CARD</sup>ISSUED 3/20/80 IP P 35 BOPD & WTR  
LKC 3702-06,  
ARB OH 3832-34

	+	+	+
	+	+	+
	+	+	+

API 15-051-21,789

SMP	TOPS	DEPTH	DATUM
ANH		1474	+ 726
BR LM		2909	- 709
TARK		3017	- 817
TOP		3201	-1001
HEEB		3448	-1248
TOR		3472	-1272
LKC		3494	-1294
BKC		3738	-1538
MARM		3762	-1562
CHT CONG		3795	-1595
ARB SD		3830	-1630
RTO		3834	-1634
<del>DDTD</del>		3950	

8-5/8" 325/175sx, 4 1/2" 3832/250sx  
1485' To Surf with 700 sks. Cement Basket 1491'

NO LOG

DST (1) 3444-3516 (TOR OP 30", REC 10' M, SIP 332/60", FP 104-104#

DST (2) 3512-34 (LKC), OP 60", 60' WM, SIP 1035/60", FP 103-207#

DST (3) 3532-54 (LKC)/60-60-60-60, 300' MSW, SIP 1117-1117#, FP 103-124/145-186#

DST (4) 3550-78 (LKC)/60-60-60-60, 360' MSW, SIP 1076-1034#, FP 41-62/187-207#

DST (5) 3580-3616 (LKC)/60-60-60-60, 30' M, SIP 1076-1076#, FP 41-41/

DST (6) 3612-40 (LKC), OP 60", 10' M, SIP 166/60", FP 41-41#

DST (7) 3636-62 (LKC)/60-60-60-60, 240' GIP, REC 30' WM W/FEW 0 SPKS, SIP 145-124#, FP 41-41/41-41#

DST (8) 3659-82 (LKC) OP 60", 5' M, SIP 51/60", FP 41-41#

DST (9) 3682-3712 (LKC)/60-60-60-60, 690' REC 60' HMCO, 210' FROGGY 0, 60' OCWM, 120' SOCMSW, 240' GSY SMCSW, SIP 725-725#, FP 62-207/248-311#

DST (10) 3713-62 (BKC, PENN), OP 60", 15' M, SIP 104/30", FP 41-41#

DST (11) 3782-3830 (MARM, CONG)/60-60-30-60, 35' OCM, SIP 1096-1096#, FP 41-41/41-41#

DST (12) 3772-3834 (MARM, CONG)/MIS-RUN

DST (13) 3712-3834 (BKC, MARM, CONG)/MIS-RUN

DST (14) 3784-3834 (MARM, CONG, ARB)/60-60-60-60, 10' OCM, 180' VSOCM, SIP 1173-1173#, FP 37-84/91-121#

MICT - CO, (ARB OH), SWB 2 BFPH, 15% O, PF (LKC) 3702-06, AC 250, SWB 6 BFPH, 77% O, POP