

To: 1 041143
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-22,289 0000
App. 1-24 W/2 NW, SEC. 10, T 34 S, R 13 W/E
4055 feet from S section line
4610 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506
Operator: Woolsey Petroleum Corporation
Name: 107 N. Market
Address: Wichita, KS 67202

Lease Name Donovan Well # C-1
County Barber 165.75
Well Total Depth 5100 feet
Conductor Pipe: Size 20 feet 65
Surface Casing: Size 8 5/8 feet 392

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address Medicine Lodge, KS

Company to plug at: Hour: 12:45 p.m. Day: 24 Month: 1 Year: 19 96

Plugging proposal received from Rick Masters

(company name) Clarke Corporation (phone) 316-886-5665

work: 4 1/2" at 5098' w/200 sx cement, PBSD 5089', Perfs at 5013-12-06, 4993-5001, 4983-87,
4914-32, CIBP at 4850', 4132-44'

1st plug sand back to 4100' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx
cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 24 Month: 1 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pushed 4 1/2" wiper plug to 4100' and sanded back on top of
wiper plug to 3950'. Put 4 sx cement on top of sand bridge through dump bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 450 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2350' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 1-30-96
INV. NO. 44759

Signed Stephen J. Pfeiffer
(TECHNICIAN)

RECEIVED
KANSAS CORP COM
JAN 26 1996
01-26-96