

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-10259-00-00  
Spot: CSENW Sec/Twnshp/Rge: 12-22S-23W  
1980 feet from N Section Line, 1980 feet from W Section Line  
Lease/Unit Name: DAN EWY A Well Number: 1  
County: HODGEMAN Total Vertical Depth: 4648 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: 100 N. BROADWAY, STE. 970  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 259 WITH 225 SX CMT  
Production: Size 5.5 feet: 4638 WITH 150 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

8151.06

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/14/2001 5:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO Phone: (785) 628-6101

Proposed Plugging Method: RUN TUBING TO BOTTOM AND SPOT 80 SX CMT & 300# HULLS. PERFORATE AT 600' AND PUMP 135 SX CMT. TIE ONTO BACKSIDE AND PUMP 25 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/15/2001 11:40 AM KCC Agent: MICHAEL MAIER

**Actual Plugging Report:**

SQUEEZED AT 4524-50' WITH 30 SX CMT, 4534' WITH 85 SX CMT. RUN TUBING TO BOTTOM AND SPOT 80 SX CMT & 300# HULLS. PERFORATE AT 600' AND PUMPED 135 SX CMT. MAXIMUM PRESSURE 200#. SHUT IN WITH 100#. TIED ONTO BACKSIDE AND PUMP 25 SX CMT. PRESSURED TO 500# AND HELD. PULLED SWEDGE. CMT FELL 700'. PUMPED 75 SX CMT AND CASING WAS FULL. STAYED FULL.

RECEIVED  
KANSAS CORPORATION COMMISSION

**INVOICED**  
DATE 6-27-01  
NO. 2001062001 CONSERVATION DIVISION  
JUN 27 2001

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Michael Maier  
(TECHNICIAN)

JUN 22 2001

[Signature]  
Form CP-13

MP