

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-10261-00-00
Spot: CSWNW Sec/Twnshp/Rge: 12-22S-23W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: DAN EWY A Well Number: 3
County: HODGEMAN Total Vertical Depth: 4400 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: 100 N. BROADWAY, STE. 970
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 9.625 feet: 243 WITH 225 SX CMT
Production: Size 5.5 feet: 4560 WITH 150 SX CMT
Liner: Size _____ feet: \$143.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/14/2001 11:20 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO Phone: (785) 628-6101

Proposed Plugging Method: PUMP 50 SX CMT & 300# HULLS. GEL SPACER TO 600'. PERFORATE AT 600'. PUMP 175 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/15/2001 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4324-36'. PUMP 50 SX CMT & 300# HULLS. PRESSURED TO 800# AND HELD. GEL SPACER TO 600'. PERFORATE AT 600'. TRIED TO PUMP INTO BUT COULDN'T. PRESSURED TO 1100# AND HELD. CHECK BACKSIDE AND FOUND HEAD WAS FULL OF CMT. 6/15/01 SWABBED DOWN TO 800' AND TOPPED OFF WITH 75 SX CMT. HOLE STAYED FULL.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 27 2001
INVOICED
DATE 6-27-01
INV. NO. 2001062001
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Michael Maier
(TECHNICIAN)

JUN 22 2001

Form CP-2/3