

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20714-00-00
Spot: N2SWSE Sec/Twnshp/Rge: 15-35S-29W
1528 feet from S Section Line, 1964 feet from E Section Line
Lease Name: ADAMS RANCH Well #: F-26
County: MEADE Total Vertical Depth: 4778 feet

Operator License No.: 34399

Op Name: QUANTUM RESOURCES MANAGEMENT, LLC

Address: 1401 MCKINNEY ST, STE 2400
HOUSTON, TX 77010

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4511 | | WITH 2 SX CMT |
| PROD | 5.5 | 4761 | 0 | WITH 350 SX CMT |
| SURF | 8.625 | 1578 | | WITH 750 SX CMT |

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/19/2012 8:30 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: WYATT YATES

Company: QUANTUM RESOURCES

Phone: (405) 574-5747

Proposed Plugging Method: 84MIRUPU, Lay down rods and pump. TOH with production tbg. Set CIBP 50 ft above the perf;s putting the CIBP @ 4,511 ft, spot 2 sks cement on plug. TIH with open ended tbg and displace the hole with 9ppg mud. Perforate casing 30 ft below the end of the surface pipe (perf @ 1,608;) (EO surface is 1,578;) Circulate cement to surface between production casing and surface casing. Fill production casing to surface with cement. Cut and cap. !!



Plugging Proposal Received By:

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/19/2012 11:30 AM

KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

SET CIBP @ 4511' WITH 2 SX CMT. TESTED CASING TO 600# FOR 15 MINUTES. LOAD HOLE WITH MUD. PERFORATE AT 1608' & PUMPED 400 SX CMT WITH 65 SX CMT CIRCULATING TO SURFACE.

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4561 | 4571 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED
OCT 25 2012
KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED

OCT 23 2012

KCC DODGE CITY