

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20142-00-00  
Spot: NENENWNE Sec/Twnshp/Rge: 25-32S-4E  
4985 feet from S Section Line, 1520 feet from E Section Line  
Lease Name: GANN Well #: 3  
County: COWLEY Total Vertical Depth: 2470 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2467		200 SX
SURF	8.625	233		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/19/2012 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.  
Proposal Rcvd. from: ALBERT COOPER Company: ALBERT COOPER/COOPER SERVIC Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS /SAND BACK @ 2300 W/5 SXS, CUT CSG, CIRC 280'-0

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/09/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/BIT & TBG CIRCULATING VARIOUS BRIDGES FROM 83'-1,890', 10-25-2012, CIRCULATED HOLE CLEAN. COPELAND ACID SERVICE MIXED & PUMPED 35 SXS CLASS A COMMON 2% CC & DISPLACED IN CASING. 10-26-2012, TAGGED CEMENT @ 1450'. 11-5-2012, RIH ON WIRELINE, SHOT SQUEEZE HOLES (2 HOLES) @ 280'-280'-1/2". RIH W/TBG @ 280'. COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 155 SXS CLASS A COMMON 2% CC TO SURFACE. CEMENT CIRCULATED ON BOTH STRINGS. PLUG DOWN 4:15 pm 11-5-2012. COPELAND ACID CEMENT TICKET # 38116. 11-9-2012, TAGGED CEMENT 44' ON SURFACE, & 71' ON CASING, TOPPED WELL BACK TO SURFACE W/20 SXS.

Perfs:

Top	Bot	Thru	Comments
2352	2357	CSG	

RECEIVED  
DEC 04 2012  
KCC WICHITA

Remarks: COMPLIANCE/ COMPLAINT

Plugged through: TBG

District: 02

Signed [Signature] (TECHNICIAN)  
12/06/12