

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20978-00-00
Spot: NWSENE Sec/Twnshp/Rge: 25-32S-4E
4442 feet from S Section Line, 368 feet from E Section Line
Lease Name: GANN Well #: 5
County: COWLEY Total Vertical Depth: 3467 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3466		250 SX
SURF	8.625	200		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2012 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.
Proposal Rcvd. from: ALBERT COOPER Company: ALBERT COOPER/COOPER SERVIC Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 11/09/2012 5:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG & BIT CIRCULATING VARIOUS BRIDGES @ 2147', RIH ON WIRELINE SHOT SQUEEZE HOLES (2 HOLES) @ 2142' - 2143'. RIH ON WIRELINE SHOT SQUEEZE HOLES (2 HOLES) 250'-251'. 11-6-2012, RIH W/TBG @2140', COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. TAGGED CEMENT @ 2040'. 11-9-2012, RIH W/TBG @ 260', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 135 SXS CLASS A COMMON 2% CC TO SURFACE. CEMENT CIRCULATED ON BOTH STRINGS. PLUG DOWN 8:30 AM 11-9-2012. COPELAND ACID CEMENT TICKET # 38123. 11-9-2012, TAGGED CEMENT @ 250' INSIDE 5.5" @ @ 90' INSIDE SURFACE. RIH W/1" TBG BETWEEN 8-5/8" & 5 1/2" CASING @ 90', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 20 SXS CLASS A COMMON 2% CC TO SURFACE. RIH W/TBG @ 245', MIXED & PUMPED 125 SXS CLASS A COMMON 2% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:30 PM 11-9-2012.

Perfs:

Top	Bot	Thru	Comments
3086	3100	CSG	


RECEIVED
DEC 04 2012
KCC WICHITA

Remarks: COMPLIANCE / COMPLAINT

Plugged through: TBG

District: 02

Signed


12/08/12 (TECHNICIAN)

JK