

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-22051-00-00
Spot: NESW Sec/Twnshp/Rge: 12-13S-31W
1930 feet from S Section Line, 2025 feet from W Section Line
Lease Name: KMB OTTLEY 12C Well #: 1
County: GOVE Total Vertical Depth: 4710 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	213		165 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/02/2012 12:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: DION Company: DUKE DRILLING CO., INC. Phone: (620) 793-0840

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 11/02/2012 2:15 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @2400 w/25 sx
2nd plug @1525 w/100 sx
3rd plug @275 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

RECEIVED
NOV 13 2012
KCC WICHITA

Remarks: ALLIED

Plugged through: DP

District: 04

Signed CASE MORRIS
11/02/12 (TECHNICIAN)

NOV 07 2012