

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23830-00-00
Spot: NWNWSWSW Sec/Twnshp/Rge: 32-15S-15W
1240 feet from S Section Line, 145 feet from W Section Line
Lease Name: HOPKINS-FUNK Well #: 1-32
County: RUSSELL Total Vertical Depth: 3600 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	729		325 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/22/2012 12:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: RANDY Company: VAL ENERGY, INC. Phone: (620) 282-1496

Proposed Plugging Method: Ordered 245 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL Witness Type: NONE
Date/Time Plugging Completed: 10/22/2012 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st plug @ 1034 w/25 sx
2nd plug @ 780 w/40 sx
3rd plug @ 460 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY (FUNK)

Plugged through: DP

District: 04

Signed Ray Dinkel (TECHNICIAN)

CM

RECEIVED
NOV 02 2012
KCC WICHITA

OCT 24 2012