

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21117-00-00
Spot: N2SESE Sec/Twnshp/Rge: 9-19S-4E
990 feet from S Section Line, 660 feet from E Section Line
Lease Name: EAST MCCARTHY Well #: 1
County: MARION Total Vertical Depth: 2375 feet

Operator License No.: 5192
Op Name: SHAWMAR OIL & GAS CO., INC.
Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2368	1750	200 SX
SURF	8.625	207		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2012 9:00 AM
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.
Proposal Rcvd. from: BENNY KEY Company: _____ Phone: (620) 382-2932

Proposed Plugging Method: As Per KCC rules and regulations

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 10/31/2012 10:00 AM KCC Agent: HUNTER CLARK

Actual Plugging Report:

SANDED OFF BOTTOM OF WELL AT 2263' WITH A 4 SX CAP. SHOT CASING OFF AT 1750' PULLED CASING. RAN TUBING TO 270' PUMPED 100 SX OF 60/40 4% 2% CC. CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2312	2320		

Remarks: CEMENT TICKET #35373 CONSOLIDATED

Plugged through: TBG

District: 02

Signed [Signature] (TECHNICIAN)

RECEIVED
NOV 28 2012
KCC WICHITA