

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22178-00-00
Spot: NW NESWNE Sec/Twnshp/Rge: 5-26S-11W
1579 feet from N Section Line, 1721 feet from E Section Line
Lease Name: RUNDELL Well #: 12
County: PRATT Total Vertical Depth: 4360 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4310	1826	WITH 165 SX CMT
SURF	10.75	241		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2012 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 4000' & 5 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 270' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 11/06/2012 10:25 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BACK TO 4000' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 625' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 283' WITH 75 SX CMT. 3RD PLUG AT 40'. CIRCULATE CMT TO SURFACE WITH 80 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4062	4126		

RECEIVED
NOV 14 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TAL TR SENT** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
11/14/12 (TECHNICIAN)

RECEIVED

NOV - 9 2012

KCC DODGE CITY