

1 070007

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,104-0000
150' S SW NW, SEC. 22, T 17 S, R 28 W/E
4140 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Cartmill Well # 2

Operator: A. Scott Ritchie
Name & Address 125 N. Market, Suite 950
Wichita, KS 67202

County Lane 150.28
Well Total Depth 4624 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 am Day: 28 Month: June Year: 19 85

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4602' PBT 4589.4', Perfs at 4383-4386'

1st plug sand back to 4330' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 200 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 am Day: 28 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx
gel, 1 sack hulls and 200 sx cement.

Maximum pressure 1000 psi and shut in 450 psi

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied.

7-9-85
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use back of this form.)

INVOICED

DATE 7-10-85

INV. NO. 8829

Signed Dan Goodnow
(TECHNICIAN)