

1 030940

4-26-88

API NUMBER 15-101-21,467-~~6000~~

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NW SW, SEC. 22, T 17 S, R 28 W/E

1650 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6761

Lease Name Cartmill Well # 1

Operator: Perry Petroleum, Inc.

County Lane 149.50

Name & Address P.O. Box 580

Well Total Depth 4600 feet

Hutchinson, KS 67504-0580

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well Gas Well Input Well SHD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Lobo Drilling Company License Number 5864

Address Box 877, Great Bend, KS 67530

Company to plug at: Hour: 4:30 a.m. Day: 26 Month: 4 Year: 19 88

Plugging proposal received from Ervin Neighbors

(company name) Lobo Drilling Company (phone) 316-792-7476

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2128-61' Elevation 2749

1st plug at 2130' with 50 sx cement, 2nd plug at 1320' with 80 sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 a.m. Day: 26 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2130' with 50 sx cement,

2nd plug at 1320' with 80 sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

5-2-88 MAY 02 1988

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED (Do not observe this plugging.)

Signed Steve Durrant (TECHNICIAN)

DATE 5-6-88

INV. NO. 20553