

1 070756

11-15

API NUMBER 15- 101-20,307-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE NE, SEC. 24, T 17 S, R 28 W&X

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Paul Well # 1

Operator: Beren Corporation

County Lane 150.22

Name & Address Box 723

Well Total Depth 4622 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 384

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Beren Corporation License Number 5364

Address Box 723, Hays, KS 67601

Company to plug at: Hour: 12:05 p.m. Day: 15 Month: 11 Year: 19 89

Plugging proposal received from Ted Crawford

(company name) Beren Corporation (phone 913-628-6101)

were: 4 1/2" at 4350' PBD 4260' Perfs at 4211-24'

1st plug at 4100' with 2 sx cement,

2nd plug pump 4 sx hulls, 10 sx gel, 75 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:10 p.m. Day: 15 Month: 11 Year: 1989

ACTUAL PLUGGING REPORT 1st plug at 4100' with 2 sx cement,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 75 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 175 sx cement.

Maximum pressure 900 psi and shut in 300 psi.

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1989
11-27-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1200' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

DATE 12-5-89

INV. NO. 26623