

To: 1 071050  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-17  
API NUMBER 15- 101-20,106-0000 127  
NE NW NE, SEC. 25, T. 17 S, R. 28 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364  
Operator: Beren Corp.  
Name & Address P.O. Box 723  
Hays, KS 67601

4950 feet from S section line  
1650 feet from E section line  
Lease Name Harlamert Well # 1  
County Lane  
Well Total Depth 4631 150.50 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Beren Corp. License Number 5364

Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 10 a.m. Day: 17 Month: 4 Year: 19 92

Plugging proposal received from Ted Crawford

(company name) Beren (phone) 913-628-6101

were: 5 1/2" at 4630' w/225 sx cement, PBTD 4591', Perfs at 4199-4571'  
1st plug pump 500 lbs. hulls and 275 sx cement down 5 1/2", displaced with water to 1300',

2nd plug perforate at 1300', pump 200 sx cement down 5 1/2",

3rd plug pump 50 sx cement down backside.

RECEIVED  
APR 24 1992  
CONSERVATION DIVISION  
WICHITA, KS  
Dan Goodrow  
(TECHNICIAN)

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 17 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 500 lbs. hulls and 275 sx cement down 5 1/2"  
and displaced with water to 1300',

2nd plug perforated at 1300', pumped 200 sx cement down 5 1/2". Maximum pressure 630 psi and  
shut in 0 psi,

3rd plug pumped 50 sx cement in backside, cement came up in bottom of cellar. Maximum  
pressure 500 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 8% gel by B.J. Services. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby certify to observe this plugging.

Signed Dan Goodrow  
(TECHNICIAN)

DATE 5-4-92

INV. NO. 35111