

To: 1 071051
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
207 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-17 API NUMBER 15- E-18,114 15-101-20129-0001 126
NE SW NE, SEC. 25, T. 17 S, R. 28 W/E

3630 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Harlamert Well # 2

Operator: Beren Corp.

County Lane

Name & Address P.O. Box 723

Well Total Depth 4629 150.44 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Beren Corporation License Number 5364

Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 6:30 p.m. Day: 17 Month: 4 Year: 19 92

Plugging proposal received from Ted Crawford

(company name) Beren Corp. (phone) 913-628-6101

were: 4 1/2" at 4628' w/150 sx cement, Perfs at 4201-4584' Squeezed holes at 1612-1741' w/300 sx

1st plug pump 500 lbs. hulls and 200 sx cement down 4 1/2" and displace with water to 1300', 1640-1741' w/150 sx

2nd plug perforate at 1300', pump 150 sx cement,

3rd plug pump 100 sx cement in backside.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 24 1992
Dan Goodrow
(TECHNICIAN)
WICHITA, KS
CONSERVATION DIVISION

Plugging Proposal Received by _____

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 8 p.m. Day: 17 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 500 lbs. hulls and 200 sx cement down 4 1/2" and

displaced with water to 1300',

2nd plug perforated at 1300' and pumped 150 sx cement. Maximum pressure 650 psi and

shut in 0 psi.

3rd plug pumped 100 sx cement in backside. Maximum pressure 230 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 8% gel by B.J. Services. No casing recovery.

(If additional description is necessary, use BACK of this form.)

(If not observed, do not observe this plugging.)

INVOICED

DATE 5-4-92

INV. NO. 35110

Signed Dan Goodrow (TECHNICIAN)