

1 050577

Docket No. D-18,114

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,156-00-00
NE SE NE, SEC. 25, T 17 S, R 28 (W/E)

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Harlamert Well # 4 SWD

Operator: Beren Corporation

County Lane 156.00

Name & Address 970 4th Financial Center

Well Total Depth 4800 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:50 am Day: 19 Month: July Year: 19 85

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4641' Perfs at 4220-32' Spot through 5 1/2" casing with mud between plugs

1st plug spot 5 sx cement on top of bridge at 1800'

2nd plug shoot off 5 1/2" at 1300' - pull back and spot 50 sx cement

3rd plug pull 200' and spot another 50 sx cement

4th plug pull to 400' and spot 50 sx cement

solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Don C. Ubel
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:30 pm Day: 22 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug spotted 5 sx cement on top of bridge at 1800', 2nd plug

spotted 50 sx cement at 1300', 3rd plug spotted 50 sx cement at 11-0', 4th plug spotted

50 sx cement at 400', 5th plug at 380' with 40 sx cement, filled with gel to 40',

6th & 7th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx
cement.

Part of the plugging operations were observed by Dan Goodrow and part by Richard W. Lacey.

Remarks: Recovered 1300' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 01 1985

INV. NO. 9249

JUL 26 1985
7-26-85

Signed Richard W. Lacey
(TECHNICIAN)