

3-5

6 031505

API NUMBER 15-195-201074-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NE NW  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SEC. 6, T 11 S, R 24 W/Ex  
4950 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767  
Operator: Ritchie Exp Inc.  
Name & Address 125 N. Market #1000  
Wichita, Ks. 67202

Lease Name Gardner P Well # 1  
County Trego 131.30  
Well Total Depth 4040 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing License Number 6050  
Address Chase, Ks.

Company to plug at: Hour: \_\_\_\_\_ PM Day: 5 Month: Mar Year: 19 91

Plugging proposal received from Monty

(company name) Kelso (phone) \_\_\_\_\_

were: 8 5/8 set at 324 w/200 sks. 4 1/2 set at 4037 w/150 sks. Topperf 3765  
PBTD 3993. Order sand and common cement. Pull pipe. Order 225 sks  
65/35 poz 10% gel 500 lbs. hulls. Allied Cement Co. Rush water trucks.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:50PM Day: 5 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sand back to 3710 w/4 sks common cement on sand w/bailer.

One shot recovered 2600 of 4 1/2 casing. Loaded hole w/cement blend from  
1900. Laid down casing. Sq 8 5/8 w/total of 225 sks cement blend  
w/500 lbs. hulls mixed into max psi 1000 lbs. Close in psi 300 lbs.

Plug complete.

RECEIVED

APR 04 1991

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-11-91  
INV. NO. 31498

*G.S.*

Signed Carl Goodrow  
(TECHNICIAN)