

2 050884

8-4

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 035-22,679-00-00
SE SW SW, SEC. 28, T 30 S, R 5 N/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5558

Lease Name J.D. Groom Well # #3

Operator: Dawson-Markwell Exploration Co.
Name & Address 3620 N.W. 58th
Oklahoma City, OK 73112

County Cowley 95.88

Well Total Depth 2950 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8-5/8 feet 220

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Butler County Drilling License Number 4421

Address Winfield State Bank, Winfield, KS 67156

Company to plug at: Hour: _____ Day: 3 Month: 8 Year: 19 89

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 4-1/2" casing set @ 2949' w/150 sx cement & perf @ 2910-15' - sand back to 2850' & dump 4 sx cement - shoot & pull casing - circulate cement from 250' to surface.

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
AUG 14 1989
8-14-89

Plugging Proposal Received by G.W.

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30p Day: 4 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT Sanded back to 2850' & dumped 4 sx cement w/dump bailer - shot & pulled 1600' of 4-1/2" casing - ran 2" tubing to 300' & circulated cement to surface.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and MIXX) observe this plugging

DATE 8-17-89

INV. NO. 25646

Signed Glenn L. Ward
(TECHNICIAN)