

1 030617

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181Operator: Donald C. SlawsonName & Address200 Douglas BuildingWichita, KS 67202API NUMBER 15- 101-21,252-0000NE NE SW, SEC. 14, T 16 S, R 30 W EX2300 feet from S section line3010 feet from E section lineLease Name Watt 'V' Well # 1County LaneWell Total Depth 4540 Mississippi 147.55 feetConductor Pipe: Size feet Surface Casing: Size 8 5/8 feet 383Abandoned Oil Well Gas Well Input Well SWD Well D&A XOther well as hereinafter indicated Plugging Contractor Slawson Drilling Co. License Number 5657Address 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202Company to plug at: Hour: 9:00 am Day: 15 Month: December Year: 19 85Plugging proposal received from Glen Base(company name) Slawson (phone) 316-263-3201Elevation 2762were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2174-47

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XOperations Completed: Hour: 12:15 pm Day: 15 Month: December Year: 19 85ACTUAL PLUGGING REPORT 1st plug at 2190' with 50 sx cement, 2nd plug at 1290' with 80sx cement, 3rd plug at 420' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10sx cement.Remarks: Used 60/40 Pozmix 6% gel by Halliburton.(If additional description is necessary, use BACK of this form.)INVOICED 11686 observe this plugging.

DEC 20 1985

DATE 11686INV. NO. 11686Signed Steve Durrant
(TECHNICIAN)DEC 20 1985
12-20-85FORM CP-2/3
Rev. 01-84

Did not
get scanned
When listing
include
Person ~~It~~ not
scanned
seriously