

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-30196-00-00
Spot: NESENE Sec/Twnshp/Rge: 18-13S-14W
3678 feet from S Section Line, 255 feet from E Section Line
Lease Name: KRUG-A Well #: 1
County: RUSSELL Total Vertical Depth: 3226 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3216		
SURF	8.625	314		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2012 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD O MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 257-3409

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 12/07/2012 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Rigged up and got down less than 15'.
12/04/2012- Drilled down with drill collars (3) and 2 joints of tubing. Pulled tubing out of well and shut down.
12/05/2012-Collars hung up in well. Worked free and started to drill and clean up well. Mudded up to carry out sand and cuttings. POOH. Shut down.
12/06/2012-Well sanded in and had to clean out well again. Drilled slowly all day with little head way made. POOH.
12/07/2012-Thinned mud down and started to drill. Hit metal off and on. Finally hit on hard metal and no more hole was being made. Hooked up to tubing and pumped 70 sx cement @ 301' and cement circulated. POOH and hooked up to casing. Pumped 35 sx cement @ 500 psi. Shut in.

GPS: 38.92479 -098.91093
NAD 83

Perfs:

RECEIVED
JAN 08 2013
KCC WICHITA

Remarks: QUALITY WELL SERVICES TICKET # 5785 CONTROL #20130041-001 KRUG A FEE FUND PROJECT

Plugged through: TBG

District: 04

Signed Ray Dinkel
(TECHNICIAN) *CM*

JAN 08 2013