

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20552-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 27-5S-22W
1485 feet from S Section Line, 1435 feet from W Section Line
Lease Name: SCHUCK Well #: A-2
County: NORTON Total Vertical Depth: 3809 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3808		
SURF	8.625	303		180 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2012 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY OIL WELL CEMENTING Phone: (620) 727-3409

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement with 700 # gel spacer and 500 # hulls.
Perforated @ 2000', 1250' and 350'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2012 6:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Perforated at 2000', 1250' and 350'.
Ran tubing to 3700' and pumped 700 # gel spacer followed by 50 sx cement w/200 # hulls.
Pulled tubing to 2025' and pumped 210 sx cement w/300 # hulls to circulate cement to surface.
Pulld all tubing. Hooked to 4 1/2" casing and pumped 175 sx cement to circulate 8 5/8" x 4 1/2" annulus to surface

RECEIVED
JAN 08 2013
KCC WICHITA

Remarks: QUALITY WELL SERVICE CONTROL # 20130053-001 SCHUCK FEE FUND PROJECT

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

JAN 08 2013