

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

7-12

2-070718

API NUMBER: 15-155-21,415-0000

NE NW NE, SECTION 22 TOWNSHIP 23 RANGE 8W

OPERATOR LICENSE # 31700 4950 FEET FROM S SECTION LINE
OPERATOR R & G OIL COMPANY 1650 FEET FROM E SECTION LINE
NAME & 23571 190TH STREET
ADDRESS ROCKFORD, IA 50463
LEASE NAME: DUNN #1-22
COUNTY: RENO
WELL TOTAL DEPTH: 3800' 123.50
PIPE: _____
SURFACE CASING: 270' OF 8 5/8"

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: DUKE DRILLING COMPANY INC

ADDRESS: 310 WEST CENTRAL, WICHITA, KS 67202 LICENSE: 5929

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 12 MONTH: 7 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: JOHN ARMBRUSTER

COMPANY NAME: DUKE DRILLING COMPANY INC PHONE: (316) 793-0840

WERE: 35 SACKS AT 1300'
35 SACKS AT 700'
330' TO SURFACE
15 IN RATHOLE
15 MOUSEHOLE

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (X)

COMPLETED: HOUR: 2:00 DAY: 12 MONTH: 7 YEAR: 1997

ACTUAL PLUGGING REPORT: CONDITIONED HOLE WITH DRILL MUD. PULLED DRILL PIPE TO 1300', PUMPED 35 SACKS. PULLED TO 700', PUMPED 35. PULLED TO 330', CIRCULATED CEMENT TO SURFACE. 15 SACKS IN RATHOLE, 15 SACKS IN MOUSEHOLE. FARMER WANTS WATER WELL.

REMARKS: 60/40 POZ 4% GEL ALLIED

I DID NOT OBSERVE THIS PLUGGING.


JACK LUTHI

RECEIVED
KANSAS CORPORATION COMMISSION

INVOICED
DATE JUL 22 1997
INV. NO. 48634

JUL 22 1997

CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3
REV. 3/90

aw