

1 070180

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,574 - 0000

NW SW SW, SEC. 22, T 17 S, R 28 W 28

990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Cartmill Well # 1

Operator: Ritchie Exploration, Inc.
Name & Address: 125 N. Market, Suite 1000
Wichita, KS 67202

County Lane 149.99

Well Total Depth 4615 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 8 Month: May Year: 19 86

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4610' PBD 4569.3' Length of shoe joint = 32.7' Perfs at 4194-4200'; 4169-78';
4128-33'; 4138-43'; 4140-4044'

Annulus squeezed from 2100' to surface

Squeeze well with 1 sack hulls, 30 sx cement, 8 sx gel, 50 sx cement, 5 sx gel, 50 sx cement and 25 sx cement on annulus or 1 sack hulls and enough econolite to fill hole from TD to surface and 25 sx cement on annulus.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 pm Day: 8 Month: May Year: 19 86

ACTUAL PLUGGING REPORT Two stage at 2100'. Pumped 1 sack hulls and 135 sx A.T.L., 11.2#

Maximum pressure 0 and on vacuum

RECEIVED STATE CORPORATION COMMISSION
MAY 19 1986
5-19-86
CONSERVATION DIVISION
Wichita, Kansas

Remarks: No recovery. Cemented by Allied. Well was left well-off - Around NA
(If additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

DATE MAY 20 1986

Signed [Signature] (TECHNICIAN)

INV. NO. 13917 5-8

1 070180

API NUMBER 15- 101-20,574-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW SW , SEC. 22 , T 17 S, R 28 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Cartmill Well # 1

Operator: Ritchie Exploration, Inc.

County Lane

Name & Address

Well Total Depth 4615 feet

125 N. Market, Suite 1000

Conductor Pipe: Size feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 8 Month: May Year: 19 86

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4610' PBT 4569.3' Length of shoe joint = 32.7' Perfs at 4194-4200'; 4169-78';
4128-33'; 4138-43'; 4140-4044'

Annulus squeezed from 2100' to surface

Squeeze well with 1 sack hulls, 30 sx cement, 8 sx gel, 50 sx cement, 5 sx gel, 50 sx
cement and 25 sx cement on annulus or 1 sack hulls and enough econolite to fill hole from
TD to surface and 25 sx cement on annulus.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00 pm Day: 8 Month: May Year: 19 86

ACTUAL PLUGGING REPORT Two stage at 2100'. Pumped 1 sack hulls and 135 sx A.T.L., 11.2#

5-16-86 - Cement dropped to 1200' - topped off well with 6 yds Ready-Mix in 5 1/2" and
8 5/8" (White Cementing)

Maximum pressure 0 and on vacuum

Remarks: No recovery. Cemented by Allied.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

STATE CORPORATION COMMISSION

JUN 16 1986

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthi
(TECHNICIAN)

STATE CORPORATION COMMISSION
JUN 02 1986
CONSERVATION DIVISION
Wichita, Kansas